



NOTE:
ALL JBL'S HOMES ARE DESIGNED FOR SETTLING. THE OWNER/CONTRACTOR MUST INSURE THAT THE HOME IS BUILT IN ACCORDANCE WITH THE CONSTRUCTION METHODS ILLUSTRATED IN THE JBL'S STANDARD DETAILS PROVIDED.

ALL SETTLING JACKS ARE BEARING POINTS AND MUST BE LOCATED OVER POST OR GANG STUDS. THESE LOCATIONS MUST CORRESPOND WITH BEARING POINTS IN THE FOUNDATION SYSTEM.

ALL INTERIOR PARTITION WALLS SHOWN ARE 3 1/2" UNLESS OTHERWISE NOTED.

ALL GLU-LAMS ARE 24F-V4 ARCHITECTURAL DOUGLAS FIR OR EQUAL UNLESS OTHERWISE NOTED.
ALL INTERIOR JACKS ARE 1".

NOTE:
ALL WINDOWS & DOORS BY NORCO.

NOTE:
1. THIS LOG PIECE TO BE SENT AS 2'-0" AND FIELD CUT TO LENGTH SPECIFIED ON 1ST WALL FRAMING PAGE.